

CITY OF KALAMAZOO

SPECIAL PROVISION

FOR

PROGRESS CLAUSE

COK

Page 1 of 1

3/25/2025

- a.** The Contractor shall submit a complete, detailed and signed, Progress Schedule, to the Engineer, utilizing MDOT form number 1130.
- b.** The progress schedule shall include, at a minimum, the controlling work items for the completion of the project and the planned dates of the work items that will be the controlling operations. All contract dates including open to traffic, project completion, interim completion and any other controlling dates in the contract must be included in the progress schedule.
- c.** After receiving Notice of Award, work can start immediately after award or on a date approved by the Project Manager. In no case, may any work be commenced prior to receipt of formal notice of award by the City.
- d.** The pavement markings on this project must be completed, including final punch-list items, and/or project clean-up on or before **December 1, 2025**.
- e.** After award, and prior to the start of work, the Contractor **must** attend a preconstruction meeting with the Engineer. The Engineer will determine the day, time and place for the preconstruction meeting. The meeting will be conducted after project award and may be rescheduled if there are delays in the award of the project. The named subcontractor(s) for, Designated and/or Specialty Items, as shown in the proposal, is/are recommended to be at the preconstruction meeting if such items materially affect the work schedule.
- f.** Liquidated Damages shall be assessed in accordance with Section 108.10 of the MDOT Standard Specifications for Construction.
- g.** The Contractor may be required to meet for a post-construction review meeting, as directed by the Engineer. The Engineer will schedule the meeting.
- h.** Failure on the part of the Contractor to carry out the provisions of this Progress Clause may be considered sufficient cause to prevent bidding future projects with the City.

CITY OF KALAMAZOO

SPECIAL PROVISION

FOR

WATERBORNE SPECIALS & LEGENDS PAVEMENT MARKINGS

COK

Page 1 of 2

3/25/2025

- a. **Description:** This work consists of providing and applying waterborne or regular dry retroreflective pavement markings in accordance with Section 811 of the Michigan Department of Transportation (MDOT) Standard Specifications for Construction and the Michigan Manual on Uniform Traffic Control Devices (MMUTCD).
- b. **Materials:** Waterborne, Low Temperature Waterborne, or Regular Dry in accordance with the seasonal limitations and minimum air temperatures from Section 811 of the MDOT Standard Specifications for Construction, Table 811-2.
- c. **Construction:** Apply pavement markings in accordance with the MDOT Standard Specifications for Construction, MMUTCD, and the MDOT Pavement Marking Standard Details (PAVE-XXX-X).
- d. **Measurement and Payment:** The completed work, as described, will be measured and paid for at the contract unit price using the following pay items:

<u>Unit Code</u>	<u>Pay Item</u>	<u>Pay Unit</u>
All: 8117001	24" Stop Bar, White	Foot
	Continental Cross Walk, White	Foot
	8' "ONLY" Legend, White	Foot
	Straight Arrow, White	Each
	Right Arrow, White	Each
	Left Arrow, White	Each
	Straight Left Arrow, White	Each
	Straight Right Arrow, White	Each
	Arrow w/Bike Symbol, White	Each
	Shared Lane Marking, White	Each
	Railroad Crossing Symbol including 24" Bands, White	Each
	"SCHOOL" Legend, White	Each
	"STOP" Legend, White	Each
	"AHEAD" Legend, White	Each
	"SLOW" Legend, White	Each

“XX MPH” Legend, White	Each
Yield Triangles	Each
Merge Arrow Markings	Each
12” Crosshatch, Yellow	Each
12” Crosshatch, White	Each
Pedestrian Symbol	Each
Speed Hump Markings	Each

Pay items include all equipment and labor required to complete the pavement markings in accordance with the MDOT Standard Specifications for Construction, MMUTCD, and the MDOT Pavement Marking Standard Details.

Speed Hump Markings item shall include all markings required for all lanes and all directions of traffic for one speed hump, including advanced warning pavement markings.